



PTR. NO. : E-89, AHMEDNAGAR

SHRI SAIBABA SANSTHAN TRUST, SHIRDI

SHIRDI : Post : Shirdi - 423 109, Tal. Rahata, Dist. Ahmednagar, Maharashtra (India)

Telephone : +91-2423-258 500, Fax : +91-2423-258 770, Telegram : Sainath, Shirdi.

NO. SSST/CONST/4065/2022

Date: - 13 JAN 2023

13 JAN 2023

To,

Sub: - Notice Inviting Quotation for Providing & fixing plywood and ACP partition and counter tables for Donation Counter at Shri Sai Prasadalya for Shri Saibaba Sansthan Trust, Shirdi.

Dear Sir,

Sealed quotations on item rate basis are invited for the following work at Shirdi for Shri Saibaba Sansthan Trust, Shirdi.

A) Bill of Quantities:

Sr. No.	Item	Quantity	Unit	Rate	Amount
1	Providing and fixing full height double skin wooden partitions made out of Frame work to be 18mm thick Commercial Plywood with maximum distance of 600mm c/c both ways(Horizontal/Vertical) or as directed , a) Laminate panelling Interior Side of partition : Providing & fixing 12mm thick Commercial plywood fixed on frame work finish with 1 mm thick laminate, b) Providing and fixing Aluminium Composite Panels (ACP)For Exterior side of Partition As Per approved equivalent make for external wall / column / canopy cladding in combination of solid / Metallic colours, including all necessary frame work and complete weather sealing. The composite panel should consist of 3mm thermoplastic core of LDPE sandwiched between 2 skins of 0.5mm thick aluminium sheet (alloy designation 310S) making a total panel thickness of 4mm. The surface will be furnished with Lumiflon based flour carbon coating on top sides and service coating on reverse side. Coatings shall conform to specifications of specifications of ECCA / AAMA and conforming to the mechanical properties of panel as per detailed technical specifications. the system shall be fixed using GI brackets and stainless steel bolts and nuts complete with spring washers and cap nuts and all other necessary accessories. all hardware shall corrosion resistant fixing on 12mm plywood as directed by the Engineer as per site conditions	199.00	Sqft		

...2/-



MUMBAI : Sainiketan, 804, - B, Dr. Ambedkar Marg, Dadar, Mumbai - 400 014

Telephone : + 91-22-24166556, Fax : + 91-22-24150798, Telegram : Sainiketan, Mumbai.

• Website : <http://www.shrisaibabasansthan.org> / www.sai.org.in • E_mail : saibaba@sai.org.in

...2...

Sr. No.	Item	Quantity	Unit	Rate	Amount
2	Providing and fixing Solid Core Flush Door Shutter of 30 mm thk. finished both side with 1 mm thk. approved colour laminate fixed to 18mm Commercial Plywood frame The rate shall be inclusive of fitting and fixing of hinges, Aldrop, door stopper, screws, cylindrical lock, tower bolt of approved make. All edges of the door to be covered with necessary lipping with polish finish. The work should be completed as per specification, design and approval of Engineer In Charge.	21.00	Sqft		
3	Providing & Fixing Donation Counter Table Size (4Wx4Hx2.5D)ft Making Frame 18mm Commercial Ply & 25mm Commercial Block Board For Top Finish With 1 mm Laminate. 2 Drawer, Storage Shutter and Shelf making 18mm Commercial ply finish with 1mm thick laminate Table. The table Front Side 12mm Ply Finished with 1mm Laminate. All inner surfaces shall be finished with laminate including the shutters. Rate shall be inclusive of all necessary approved fittings like hinges, locks, handles, tower bolts and any necessary hardware items. The work should be completed as per specification, design and approval of Engineer In Charge.	2.00	Nos		
4	Providing & Fixing Donation Counter Table Size (4Wx4Hx2.5D)ft Making Frame 18mm Commercial Ply & 25mm Commercial Block Board For Top Finish With 1 mm Laminate .All inner surfaces shall be finished with laminate including the shutters. Rate shall be inclusive of all necessary approved fittings like hinges, locks, handles, tower bolts, and any necessary hardware items. The work should be completed as per specification, design and approval of Engineer In Charge.	1.00	Nos		
5	Providing & Fixing Wooden Shelf/ Back light Frame For Design As per Design making with 18mm thk commercial Ply Finish with approved 1mm thk laminate shade. complete and approved by Engineer In Charge.	30.00	Sqft		
6	Supplying and fixing rolling shutter of approved make, made of 80 x 1.25 mm thick M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of 1.25 mm thick for rolling shutters. Rate to include providing fixing of ball bearing for rolling shutter.	130.00	Sqft		

...3/-



SHRI SAIBABA SANSTHAN TRUST, SHIRDI

SHIRDI : Post : Shirdi - 423 109, Tal. Rahata, Dist. Ahmednagar, Maharashtra (India)

Telephone : +91-2423-258 500, Fax : +91-2423-258 770, Telegram : Sainath, Shirdi.

Sr. No.	Item	Quantity	Unit	Rate	Amount
7	Gypsum Board False Ceiling: Providing and fixing in position Gypsum board false ceiling with 12.5 mm thick Gypsumboards ,screwed/fixd to the understructure of suspended G.I. Grid constructed and suspended from the main ceiling consisting of ceiling sections of size 25x50mm maximum center to center distance of 600 milimeter perimeter channel and intermediate channel sat maximum center to center distance 1200 milimetre galvanized grid should be fixed to reinforced cement concrete slab. The gypsum board should be fixed to galvanized iron grid with necessary screws. The boards should be taped and filled from under side to give smooth, seamless ceiling. The rate should include necessary additional ceiling sections and intermediate channels. Additional intermediate channels should be fixed to straph angers for additional support to prevent strapping at every 1200 milimetre item to be competed in all respect including necessary sleeves for ducts finishing of joints cut outs, lifts etc. all complete.	120.00	Sqft		
8	Providing and applying Two coats of Plastic Emulsion of approved make in approved shade and texture including surface preparation consisting of cleaning the surface to be painted using brush and sand the surface using emery paper 180 to remove all the loose particles, smoothen the surface with 2 coats Cement wall Putty, allow drying for 4 to 6 Hours, sand the surface with emery paper 180 and apply a coat of Primer and allow it to dry for 6 to 8 Hours. and including scaffolding, scraping, brushing, cleaning and including one coat of primer and Palti etc complete as per the manufacturer's specifications and to the entire satisfaction of Engineer In Charge..	120.00	Sqft		
9	Providing and fixing 12mm ply at top of Ceiling On MS Frame. With All necessary Supporting Required Make - Century, kit ply, Anchor, Green ply.	120.00	Sqft		
10	Providing and fixing Wallpaper over 4mm MDF board having Bulk Density of 750 kg per cubic meter and Grade-1 as per IS: 12406-2003 Edition 2.2. 4mm MDF Fix Over the Existing ACP Finished Wall as directed by Architect/Engineer etc. complete.	100.00	Sqft		
11	75mm Aluminium Skirting -Supplying, fitting and fixing 75mm Alu skirting with rubber profile and PVC connectors with the screw complete in all respect with requisite accessories like end profile, transition profile, etc., wherever required. (This work should not be executed without specific permission of Engineer In Charge).	44.00	Rft		
12	Electrical Work	120.00	Sqft		

B) Terms & Conditions:

1. The rates mentioned shall be inclusive of GST.
2. The rates shall be firm and shall not subject to variations.

...4/-

**MUMBAI :** Sainiketan, 804, - B, Dr. Ambedkar Marg, Dadar, Mumbai - 400 014

Telephone : + 91-22-24166556, Fax : + 91-22-24150798, Telegram : Sainiketan, Mumbai.

• Website : <http://www.shrisaibabasansthan.org> / www.sai.org.in • E_mail : saibaba@sai.org.in

Telephone: 020 2431 2000 Fax: 020 2431 2001

...4...

3. Sealed Quotations shall be submitted to the Inward Department of the Sansthan at Shirdi, upto 5:00 pm on ___/___/2022.
4. The Period for completion of the work shall be (30 days) One Month from the date of work order.
5. Bidder should submit GST registration certificate copy.
6. Quantities in BOQ are approximate and may vary according to requirement. Bill will be paid as per the measurement of work executed.

Sansthan Administration reserves the right to reject any or all quotations without assigning any reasons thereof.

Thanking you.



(B. D. Dabhade)
Executive Engineer,
Shri Saibaba Sansthan Trust (Shirdi)