

Shri Saibaba Sansthan Trust, Shirdi.
Construction Department,
Date: 09/12/2021.

Corrigendum to be published on Sansthan's Website.



SHRI SAIBABA SANSTHAN TRUST, SHIRDI

Tal. Rahata, Dist. Ahmednagar, (MS) - 423109.


Tel: (02423) 258899, Fax: 258870.

E-mail: construction@sai.org.in, Website: www.sai.org.in.

CORRIGENDUM NOTICE

With reference to the Notice Inviting Quotations No.SSST/CONST/2771/2021, dtd.22/11/2021 and the same published on Sansthan's website for the work of Providing & Laying Pipeline for Rainwater at Shri Saibaba Hospital, Shirdi, it is hereby notified that the date of submission of sealed quotations is hereby extended upto 20/12/2021.

Shri Saibaba Sansthan Trust, Shirdi reserves the right to reject any or all quotations without assigning any reasons therefor.


(S. M. Jori)

I/c Executive Engineer,
Shri Saibaba Sansthan Trust, Shirdi.





PTR. NO. : E-69, AHMEDNAGAR

SHRI SAIBABA SANSTHAN TRUST, SHIRDI

SHIRDI : Post : Shirdi - 423 109, Tal. Rahata, Dist. Ahmednagar, Maharashtra (India)

Telephone : +91-2423-258 500, Fax : +91-2423-258 770, Telegram : Sainath, Shirdi.

NO.SSST/CONST/277/2021.
Date: 22 NOV 2021

To,

Sub: Notice Inviting Quotation for Providing & Laying Pipeline for Rainwater in Open Space in Front of Shri Saibaba Hospital, Shirdi.

Dear Sir,

Sealed item rate quotations are invited for the following work at Shri Saibaba Hospital Shirdi, subject to the terms and conditions mentioned below,

A) Bill of Quantities:

S.No.	Description	Qty.	Unit
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfilling, ramming, watering including shoring and strutting etc. complete. (Lift upto 3.0 m) By Manual Means. SSR P.No.115, I.No.21.01.	10.80	Cum
2	Providing and laying Cast in situ / Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying / pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR P.No.131, Item No.24.01.	2.25	Cum
3	Removing cement tiles or marble or polished shahabad floor or dado without bed concrete including stacking the materials as directed with all leads, lifts etc. complete. SSR P.No.215, Item No.46.19, Spec. No. Bd. BDW 8.	24.00	Sqm
4	Providing and fixing the existing factory made Hydraulically pressed Mechanically vibrated and compacted precast interlocking cement concrete paving blocks 60mm thick of approved size and shape as specified including cost of all materials, transportation of blocks to work site including loading, unloading and stacking as directed, laying paving blocks in position over prepared bed of natural sand / crushed sand of 50mm thickness including, spreading blindage of fine sand over the prepared bed, compacting blocks by plate vibrator etc. complete. (Labour Rate only).	24.00	Sqm

..2/-.



MUMBAI : Sainiketan, 804, - B, Dr. Ambedkar Marg, Dadar, Mumbai - 400 014

Telephone : + 91-22-24166556, Fax : + 91-22-24150798, Telegram : Sainiketan, Mumbai.

• Website : <http://www.shrisaibabasansthan.org> / www.sai.org.in• E_mail : saibaba@sai.org.in

D:\SBG\GSJ WORKSHOSPITAL DRAINAGE WORKKIT FOR RAIN WATER PIPELINE.DOC

S.No.	Description	Qty.	Unit
5	Removing rich mix cement concrete including stacking the spoils as directed with all leads, lifts etc complete. SSR P.No.215, Item No.46.13, Spec.No. Bd.BDW 8.	2.70	Cum
6	Providing and constructing Brick Masonry Inspection Chamber 60cm x 45cm x 90cm including 1:4:8 cement concrete foundation 1:2:4 cement concrete channels half round G.S.W. pipes, Brick Masonry, plastering from inside and with frame fixed in cement concrete with RCC Cover medium duty 140 Kilogram with frame etc complete. SSR P.No.200, I.No.42.12, Spec. No. Bd.BDV43.	04	Nos.
7	Providing, laying and fixing, jointing Eco-drain 160 mm SN 4 Nu-Drain Upvc pipes or of equivalent make, manufacture as per EN 13476 or equivalent as per I.S.15328 with fittings such as bends, tees, coupler etc, jointing with rubber lubricant including necessary excavation, trench refilling with selective excavated material etc. complete. SSR P.No.211, I.No.43.31, Spec. No. Bd.BDV.	40.00	Rmt

B) Terms and Conditions:

1. The rates for above work shall be inclusive of GST, all material, labour, transport etc. complete.
2. The bidder shall furnish the copy of GST Registration along with the quotation.
3. The rates quoted shall be firm & no escalation of rates will be entertained till completion of work after issue of work order.
4. Defects Liability period will be for 12 months for above mentioned work.
5. Quantities in BOQ are approximate and may vary according to the requirement. Bill will be paid as per the measurement of actual work executed on site.
6. No advance payment will be given against the work order. Bill will be paid after submission of R. A. bill / Final Bill and as per the actual quantity executed on site.
7. 75% Advance will be payable on submission of R. A. / Final Bill. Balance amount will be paid after deduction of advance amount.
8. Minimum Value for Interim Bill Certificate is Rs.50,000/-.
9. The date of commencement shall be 15 days from date of issue of work order.
10. The time for completion shall be 30 days from the date of commencement after issue of work order.
11. Material shall be strictly used as per the specifications and makes with prior approval of Sansthan.
12. Water & Electricity required for the work shall be made available at one point by Sansthan.
13. 5% Total Security Deposit will be recovered from the bills. Which will be returned after 12 months of DLP.
14. Validity of quotation - 90 days from last date for submission of sealed quotation and to be extended if required.
15. Liquidated Damages - The liquidated damages to be recovered will be Rs.500/- per delayed day. The total amount of Liquidated damages / Penalty to be paid under the provisions of this clause shall not exceed five percent (5%) of the total Contract amount.
16. The bidders are requested to submit their Bank details (RTGS) along with the quotation document.
17. Bidders are requested to submit the final lowest rates for this work.

...3/-



SHRI SAIBABA SANSTHAN TRUST, SHIRDI

SHIRDI : Post : Shirdi - 423 109, Tal. Rahata, Dist. Ahmednagar, Maharashtra (India)
Telephone : +91-2423-258 500, **Fax :** +91-2423-258 770, **Telegram :** Sainath, Shirdi.

...3...


18. The quotation shall be written on a letterhead of your firm and shall be submitted in a sealed cover superscribing as "Quotation for Providing & Laying Pipeline for Rainwater in Open Space in Front of Shri Saibaba Hospital, Shirdi". The reference no. & date of this NIQ shall be mentioned on the envelope. It shall be addressed to **Chief Executive Officer, Shri Saibaba Sansthan Trust, Shirdi, Tal.- Rahata, Dist.- Ahmednagar.**
19. Your quotation should reach at our Shirdi Office on or before / /2021 before 05:00 PM after receipt of this NIQ.

C) Makes:

- 1) Cement – Ultra Tech, Ambuja, Birla Gold, ACC.
- 2) Eco Drain Pipes – Supreme, Prince, Finolex, Astral, Jain.

Shri Saibaba Sansthan Trust, Shirdi reserves the right to reject any or all quotations without assigning any reasons therefor.

Thanking you.


20.11.21

(S. M. Jori)

I/c Executive Engineer,
Shri Saibaba Sansthan Trust, Shirdi.



MUMBAI : Sainiketan, 804, - B, Dr. Ambedkar Marg, Dadar, Mumbai - 400 014
Telephone : + 91-22-24166556, Fax : + 91-22-24150798, Telegram : Sainiketan, Mumbai.

• **Website :** <http://www.shrisaibabasansthan.org> / www.sai.org.in • **E_mail :** saibaba@sai.org.in