

SHRI SAIBABA SANSTHAN TRUST, SHIRDI

SHIRDI : Post : Shirdi - 423 109, Tal. Rahata, Dist. Ahmednagar, Maharashtra (India)

Telephone : +91-2423-258 500, Fax : +91-2423-258 770, Telegram : Sainath, Shirdi.

NO.SSST/CONST/ 2856 /2024.

Date: 18 NOV 2024

To,

Sub:Notice Inviting Quotation for Proposed Shed extension for Bundi Kitchen at Shri SaiPrasadalaya Shirdi.

Dear Sir,

Sealed quotations are invited from reputed Contractors for the following work as mentioned below,

Sr. No	Description	Total Qty	Unit
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 0.00 to 1.50 m.) By Manual Means (21.01)	4.000	Cum.
2	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.(21.38)	11.340	Cum.
3	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) foundation (24.01)	0.540	Cum.
4	Providing and laying Cast in situ/Ready Mix cement concrete in M15 of trap/ granite/quartzite/gneiss metal for foundation / steps including steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. complete. The Cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface, only. Newly laid concrete shall be covered by gunny bag, plastic, tarpaulin etc. (Wooden centering will not be allowed.),with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) Flooring (24.04)	6.860	Cum.

**MUMBAI** : Sainiketan, 804, - B, Dr. Ambedkar Marg, Dadar, Mumbai - 400 014

Telephone : + 91-22-24166556, Fax : + 91-22-24150798, Telegram : Sainiketan, Mumbai.

• Website : <http://www.shrisaibabasansthan.org> / www.sai.org.in • E_mail : saibaba@sai.org.in

Sr. No	Description	Total Qty	Unit
5	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in foundations and plinth of inner walls/ in plinth external walls including bailing out water manually , striking joints on unexposed faces, raking out joints on exposed faces and watering etc. Complete.(27.01)	11.730	Cum.
6	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	9.660	Cum.
7	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.(21.37)	54.860	Cum.
8	Carting Debries & throwing at dumping yard or any other authorised place including required materils as directed with all leads, lifts etc. .	13.720	Cum.
9	Dismantling brick masonry in lime or cement mortar and stacking the materils as directed with all leads, lifts etc.(1540)-planter removal	1.380	Cum.
10	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete.(32.04)	52.000	Sqm.
10	Providing and laying polished hand cut Kotah Stone flooring 25mm to 30mm thick and 45cm to 55cm wide in plain/diamond pattern on a bed of 1:6 C.M. including cement float, filling joints with neat cement slurry, curing, polishing and cleaning complete.	78.000	Sqm.
11	Providing and fixing of colour coated Zinaluminium(R) AZ150 (min 150 gms/sq.mt. total on each side) profiled sheets for roofing. The feed material is manufactured out of nominal 0.45 mm Base Metal Thickness (BMT) (0.5 mm TCT), Hi-strength steel with min.550 MPa yield strength, metallic hot dip coated withAluminium-Zinc alloy (55% aluminiumm 43.4% zinc 1.6% silicon) with COLORBOND (R) steel quality super durable polyster paint coat (with inorganic pigment). The paint shall have a total coating thickness of nominal 35 mm, comprising of nominal 25mm exterior coat on top surface and nominal 10 um reverse coat on back surface. Profile sheet shall have nom. 950-1050 mm effective cover width and nominal 25-30 mm deep ribs with sublet square fluting in the five pan at nominal 180-250 mm center- to-center. The end rib shall be designed for anti-capacity groove. and return leg. The feed material should have coil manufacturers product details marked a regular interval. including fasteners with min. fastened with min. 25 um Zinc-Tin alloy coated, Hex head, self-drilling screw etc. complete. (weight of profile 4.52 Kilogram/ One Square Metre) 600 mm girth (Surface Width). (1180) Including scaffolding, work on zulla etc comp.	76.650	Sqm.

SHRI SAIBABA SANSTHAN TRUST, SHIRDI

SHIRDI : Post : Shirdi - 423 109, Tal. Rahata, Dist. Ahmednagar, Maharashtra (India)

Telephone : +91-2423-258 500, Fax : +91-2423-258 770, Telegram : Sainath, Shirdi.

TERMS AND CONDITIONS-

1. The above rates shall be for completed item inclusive of GST and transport. The rates once quoted shall be firm & no escalation of rates will be entertained.
2. The Successful bidder has to Earnest Money Deposit - Rs.5,000/- by Cash/D.D. within 7 days of date of work order. Balance SD will be recovered from RA Bill. Total SD - 5% of Contract amount. SD will be released after 3 months after date of completion of work.
3. Quantities are approximate and may vary according to requirement. Bill will be paid as per the actual work done.
4. No advance will be paid against work order. Bill will be paid after completion of all work and upon submission of GST invoice bill.
5. The time for completion of work shall be 15 days from the date of issue of the work order.
6. Material shall be strictly as per the above description, specifications mentioned above & prior approval of Engineer In Charge.
7. In case of any dispute between the parties, the jurisdiction shall vest at Rahata court only.
8. The bidders are requested to submit their Bank details and copy of PAN card, EPF No., and GST Registration No. along with the quotation.
9. The quotation shall be addressed to The Chief Executive Officer, Shri Saibaba Sansthan Trust, Shirdi, Tal.-Rahata, Dist.-Ahmednagar and written on a letterhead of your firm and shall be submitted on or before 25/11 /2024 in a sealed cover superscribing as "**Quotation for Proposed Shed extension for Bundi Kitchen at Shri SaiPrasadalaya Shirdi.**"

Thanking you.

Yours Sincerely,


I/C. Executive Engineer,
Shri Saibaba Sansthan Trust, Shirdi.

