

**SHRI SAIBABA SANSTHAN TRUST, SHIRDI**

SHIRDI : Post : Shirdi - 423 109, Tal. Rahata, Dist. Ahmednagar, Maharashtra (India)  
Telephone : +91-2423-258 500, Fax : +91-2423-258 770, Telegram : Sainath, Shirdi

NO. SSST/CONST/ 827 /2021  
Date: -

To,

12 JUN 2021

**Sub: - Notice Inviting Quotation for Providing & laying Paving Block and construction of exit gate at Shri Sai Prasadalya, Shirdi.**

Dear Sir,

Sealed quotations on item rate basis are invited for the following work at Shirdi for Shri Saibaba Sansthan Trust, Shirdi.

**A) Bill of Quantities:**

Sr.No.	Description	Qty	Unit	Rate	Amount
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 3.00 m.) By Manual Means SSR 2020-21, Page No.148, Item. No. 21.01	63.45	CUM		
2	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete. SSR 2020-21, Page No.152, Item. No. 21.38	38.30	CUM		
3	Providing and fixing heavy duty inter locking concrete RUBBER MOULD GLOSSY PAVING BLOCKS of 60 millimeter thickness of having a strength of 400 Kilogram/sq.m of approved quality and shape on a bed of crushed sand of 25 to 30 millimeter thick including striking joints and cleaning etc. complete. (using 100% crushed sand) SSR 2020-21, Page No.211, Item. No. 33.53	162.00	SQM		
4	Providing and casting in situ or precast tapering R.C.C. M-20 Barrier type Kerb without gutter (as per IRC 86 1983) embedded 125mm below ground level over M-10 PCC finished neatly with C.M. 1:2, setting the same in C.M. 1:2, including the required excavation in any strata and removing the excavated stuff any where in city and redoing the surface as specified and directed by Engineering In-charge. Using Concrete Batching and Mixing Plant. SSR 2020-21, Page No.69, Item. No. 7.01	54.00	Rmt		

....2/-

Sr.No.	Description	Qty	Unit	Rate	Amount
5	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. beams and lintels as per detailed designs and drawings or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction and roughening the surface if special finish is to be provided and curing etc. complete. (Excluding reinforcement and structural steel). with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade)SSR 2020-21, Page No.175, Item No. 25.75	1.60	CUM		
6	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap/ granite / quartzite/ gneiss metal for R.C.C. slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete.(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR 2020-21, Page No.176, Item. No. 25.70	2.55	SQM		
7	Providing and laying in situ /Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. work in foundations like raft, strip foundations, grillage and footings of R.C.C. columns and steel stanchions etc. including bailing out water, Steel centering formwork, laying/pumping cover blocks, compaction and curing roughening the surface if special finish is to be provided (Excluding reinforcement and structural steel) etc. complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR 2020-21, Page No.172, Item . No. 25.11	1.73	CUM		
8	Providing and laying Cast in situ/Ready Mix cement concrete M-20 of trap / granite /quartzite/ gneiss metal for R.C.C. columns as per detailed designs and drawing or as directed including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete.(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Crushed sand VSI Grade) SSR 2020-21, Page No.173, Item . No. 25.31	0.46	Cum		

**SHRI SAIBABA SANSTHAN TRUST, SHIRDI**

**SHIRDI :** Post : Shirdi - 423 109, Tal. Rahata, Dist. Ahmednagar, Maharashtra (India)  
**Telephone :** +91-2423-258 500, **Fax :** +91-2423-258 770, **Telegram :** Sainath, Shirdi.

...3...

Sr.No.	Description	Qty	Unit	Rate	Amount
9	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete. SSR 2020-21, Page No.201, Item No. 32.11	4.02	Sqm		
10	Providing and applying two coats of exterior weather shield paint of approved manufacture and of approved colour to the plastered surfaces including cleaning, preparing the plaster surface, applying primer coat, scaffolding if necessary, and watering the surface for two days etc complete. NOTE: For Item Number 15 to 18 prior approval of Superintending Engineer will be necessary. SSR 2020-21, Page No.217, Item No. 35.26	4.02	Sqm		
11	Providing and fixing mild steel grill gate as per the detailed drawing including hinges, locking arrangements and painting in three coats of oil paint of approved colour and shade etc. complete.(weight 18 Kilogram. to 20 Kilogram. Per Sq.m.) Spec. Number: As directed by Engineer- in-charge. SSR 2020-21, Page No.168, Item No. 23.09	9.00	Sqm		
12	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete	0.5	MT		
				Total Amount Rs.-	

**B) Terms & Conditions:**

1. The rates mentioned shall be inclusive of GST.
2. The rates shall be firm and shall not subject to variations.
3. Sealed Quotations shall be submitted to the Inward Department of the Sansthan at Shirdi, upto 5:00 pm on 19/06/2021.
4. The Period for completion of the work shall be (02) two months from the date of work order.
5. Bidder should submit GST registration certificate copy.
6. The bidder should be registered with Employees Provident Fund Organization, he should submit the relevant documents for the same.
7. Quantities in BOQ are approximate and may vary according to requirement. Bill will be paid as per the measurement of work executed.

Shri Saibaba Sansthan Trust (Shirdi) reserves the right to reject any or all quotations without assigning any reasons thereof.

Thanking you.

*Sainath*  
12.6

**I/c. Executive Engineer,  
Shri Saibaba Sansthan Trust (Shirdi)**