

रजि.नं. : ई-६९, अहमदनगर



श्री साईबाबा संस्थान विश्वस्तव्यवस्था, शिर्डी

शिर्डी : पोस्ट : शिर्डी - ४२३ १०९, ता. राहाता, जि. अहमदनगर, महाराष्ट्र (भारत).

दुरध्वनी : +९१-२४२३-२५८ ५०० फॅक्स : +९१-२४२३-२५८ ७७०, टेलिग्राम : साईनाथ, शिर्डी.

जा.नं.एसएसएसटी/बांधकाम/२३००/२०२२

दिनांक:- 10 SEP 2022

10 SEP 2022

प्रती,

विषय : श्री साईबाबा भक्तनिवासस्थान (५०० रुम) शेजारील वाहनविभागाकडे जाणा-या रस्त्याचे पुर्वेकडील बाजूचे वापरात नसलेले सार्वजनिक प्रसाधनगृहाचे नूतनीकरण करणेकामी कोटेशन देणेबाबत .


श्री साईबाबा भक्तनिवासस्थान (५०० रुम) शेजारील वाहनविभागाकडे जाणा-या रस्त्याचे पुर्वेकडील बाजूचे वापरात नसलेले सार्वजनिक प्रसाधनगृहाचे नूतनीकरणासाठी कोटेशन मागविण्यात आले आहेत. त्याबाबतचा तपशिल दर्शविणारी कोटेशन मागणी सूचना (Notice Inviting Quotation) सोबत जोडली आहे. कामानाबतची माहिती संस्थानचे बांधकाम विभागात उपलब्ध आहे. तरी उपरोक्त प्रमाणे कामासाठी दराचे सिलबंद कोटेशन त्वरीत देण्याचे करावे हि विनंती.

(बी.डी.दाभाडे)

कार्यकारी अभियंता,

श्री साईबाबा संस्थान विश्वस्तव्यवस्था, शिर्डी

सोबत - कोटेशन मागणी सूचना (Notice Inviting Quotation)



मुंबई साईनिकेतन, ९०४, ६, डॉ. आंधेकर मार्ग, दादर, मुंबई - ४०० ०१४

दुरध्वनी : +९१-२२-२४१६६५५६ फॅक्स : +९१-२२-२४१५०७९८. टेलिग्राम - साईनिकेतन, मुंबई.

• Website : <http://www.shrisaibabasansthan.org> / www.sai.org.in • Email : saibaba@sai.org.in

NO.SSST/CONST/ /2019.
Date:

To,

Sub: Notice Inviting Quotation for Proposed Vehicle Dept. Office by Renovating Existing General Toilet Unit at S.No.109, Shirdi (Saibaba Bhakta niwas-500 Room East side) for Shri Saibaba Sansthan Trust, Shirdi.

Dear Sir,

Sealed Percentage rate quotations are invited for the following work at Shirdi, subject to the terms and conditions mentioned below,

A) Bill of Quantities:

Sr.No.	Description	Quantity	Unit	Rate	Amount
1	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete (890)	0.7245	Cum.	8933	6471.67
2	Dismantling brick masonry in lime or cement mortar and stacking the materials as directed with all leads, lifts etc.	5.67	Cum.	371.7	2107.54
3	Providing internal cement plaster 12mm thick in single coat in cement mortar 1:4 without neeru finish to concrete or brick surfaces, in all positions including scaffolding and curing etc. complete.+ Providing neeru finish to plastered surfaces in all positions including scaffolding and curing etc. complete.(956,964)	18.9	Sqm.	383.5	7248.15
4	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1Kilogramper cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.(961)	2.25	Sqm.	383.5	862.88
5	Providing and laying Vitrified MATT finish having decorative type of size 600 millimeter x 600 millimeter of 8 to 10 millimeter thickness (on a existing flooring) with bonding chemical and confirming to IS 156222006 (Group Bla) of approved make shade and pattern for flooring in required position laid on a bed of bonding chemical filling joints curing and cleaning etc. complete.(1044) (Tile Basic Rate- 938 per Sqm.)	75.25	Sqm.	1901	143048.75

Sr.No.	Description	Quantity	Unit	Rate	Amount
6	Providing and applying washable oil-bound distemper of approved colour and shade to old and new surfaces in two coats including scaffolding, preparing the surfaces. (excluding the primer coat.) etc. complete. (1107,1110,1088)	324	Sqm.	50.74	16439.76
7	Providing and applying two coats of flat oil paint of approved colour to the old structural steel work and iron work previously painted in building including scaffolding, if necessary, cleaning and preparing the surface (excluding primer coat) etc. complete.(1077)	4.50	Sqm.	94.4	424.80
8	Providing and applying two coats of textured synthetic paint of approved shade and quality and one coat of primer before applying textured paint including scaffolding if necessary preparing surface by thoroughly cleaning oil, grease, dirt and other materials as required, etc. complete.	165.00	Sqm.	174.6	28815.60
9	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to a distance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 3.00 m.) By Manual Means(718)	15.00	Cum.	273.8	4106.40
10	Providing dry/ trap/ granite/ quartzite/ gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc. complete.	15.00	Cum.	1527	22903.80
11	Providing and fixing heavy duty inter locking concrete Coloured paving blocks of 60 mm thickness of having a strength of 300 Kilogram/Sq.cm. of approved quality and shape on a bed of crushed sand of 25 to 30 mm thick including skirting joints and cleaning etc. complete	100	Sqm.	1062	106200.00
12	Providing and fixing solid core flush door shutter in single leaf 32 mm thick decorative type of exterior grade as per detailed drawings approved face veneers 3 mm thick on both faces or as directed, all necessary beads, mouldings and lipping, wrought iron hold fasts, chromium plated fixtures and fastenings, with brass mortise lock, chromium plated handles on both sides, and finishing with French Polish etc. complete.(1200) - Incl. Providing and fixing 100mmx75mm RCC M40 door frame with painting etc complete	5.67	Sqm.	3776	21409.92

Sr.No.	Description	Quantity	Unit	Rate	Amount
13	Removing all urinal, pans or wash hand basins with frame including disconnecting the sanitary and water supply connections, removing the same carefully and stacking the serviceable materials as and where directed including throwing the unserviceable materials outside etc complete(1562)	2	Unit	1180	2360.00
14	Providing and erecting chain link fencing 1.6 M. height with G.I. chain link of size 50 x 50 mm, 8 gauge thick and fixed 75 mm above ground level on vertical M.S. Angles of 40 x 40 x 6 mm size, including excavating pits for foundation and embedded in C.C. block of 1:4:8 mix of size 450 x 450 x 670 mm. at 1.75 M. c/c with iron bar 16mm dia as hold fast including welding link with angle frame at 30 cm c/c with nuts and bolts and horizontal M.S. Angles at top and bottom of 25 x 25 x 5 mm size and vertical M.S. flat 35 x 5 mm and 25 x 5 mm horizontal including cross support of 40 x 40 x 6 mm angles both side at every corner or bend embedded in concrete blocks of 1:4:8 of size 450 x 450 x 670 mm including 3 coats of oil painting etc. complete.	30	Rmt.	2721	81632.40
15	Providing and fixing M.S. grill door 24 Kilogram/Square Metre of various size as per detailed drawings without hot dip coating, iron fixtures and fastenings and 3 coats of oil painting etc	3.84	Sqm.	3579	13743.13
16	Providing and fixing colour coated Zinalume (R) AZ150 (min 150 gms/sq.mt. total on each side) profiled sheets for roofing. The feed material is manufactured out of nominal 0.45 mm Base Metal Thickness (BMT) (0.5 mm TCT), Hi-strength steel with min.550 MPa yield strength, metallic hot dip coated with Aluminium-Zinc alloy (55% aluminium 43.4% zinc 1.6% silicon) with COLORBOND (R) steel quality super durable polyester paint coat (with inorganic pigment). The paint shall have a total coating thickness of nominal 35 um, comprising of nominal 25 um exterior coat on top surface and nominal 10 um reverse coat on back surface. Profile sheet shall have nom. 950-1050 mm effective cover width and nominal 25-30 mm deep ribs with subtle square fluting in the five pan at nominal 180-250 mm center- to-center. The end rib shall be designed for anti-capillary groove. and return leg. The feed material should have coil manufacturers product details marked a regular interval. Including fasteners with min. fastened with min. 25 um Zinc-Tin alloy coated, Hex head, self-drilling screw etc. complete. (weight of profile 4.52 Kilogram/Square Metre)(1172)	10.95	Sqm.	1505	16474.28

Sr.No.	Description	Quantity	Unit	Rate	Amount
17	Providing and fixing in position. (as per I.S.1868 / 1982) Aluminium sliding window of two tracks with rectangular pipe having overall dimension 63.50 x 38.10 x 1.02 mm at weight 0.547 Kilogram/One Running Metre. and window frame bottom track section 61.85 x 31.75 x 1.20 mm at weight 0.695 Kilogram/One Running Metre. Top and side track section 61.85 x 31.75 x 1.30 mm at weight 0.659 Kilogram/One Running Metre. The shutter should be of bearing bottom 40 x 18 x 1.25 mm at weight 0.417 Kilogram/One Running Metre. Inter locking section 40 x 18 x 1.10 mm at weight 0.469 Kilogram/One Running Metre. And handle section 40 x 18 x 1.25 mm at weight 0.417 Kilogram/One Running Metre. and top section 40 x 18 x 1.25 mm at weight 0.417 Kilogram/Running metre. As per detailed drawings and as directed by Engineer in charge with all necessary Aluminium sections fixtures and fastenings such as roller bearing in nylon casting and self locking catch fitted in vertical section of shutter including 5 mm thick plain glass with all required screws and nuts etc, complete. With powder coating without box	3.24	Sqm.	5740	18596.04
	Total Rs.				492845.11
	Percentage above/Below				
	Total Rs.				

B) Terms and Conditions:

1. The above rates shall be inclusive of GST, material, labour, transport etc. complete.
2. The bidder shall furnish the copy of GST Registration.
3. The rates quoted shall be firm & no escalation of rates will be entertained till completion of work after issue of work order.
4. Site: Shri Saibaba Bhakta niwas-500 Room Area) Shirdi.
5. Defects Liability period will be for 03 months for above mentioned work.
6. Quantities in BOQ are approximate and may vary according to the requirement. Bill will be paid as per the measurement of work executed.
7. No advance payment will be given against the work order. Bill will be paid after submission of R. A. / Final Bill and as per the actual quantity executed on site.
8. The date of commencement shall be 10 days from date of issue of work order.
9. The time for completion shall be 30 days from the date of commencement after issue of work order.
10. Material shall be strictly used as per the specifications, with prior approval of Sansthan.
11. Electricity required for the work shall be made available at one point by Sansthan.
12. 5% Security Deposit will be recovered from the bills. Which will be returned after 03 months of DLP.
13. The bidder is bound by the Contract Labour (Regulation & Abolition) Act, 1970 and rules framed there under. The bidder shall furnish copy of EPF registration. The bidder shall deposit the amount of employer's contribution of EPF and furnish the copies of challans.
14. Validity of quotation - 90 days from last date for submission of sealed quotation and to be extended if required.

15. Liquidated Damages - The Liquidated damages to be recovered will be Rs.500/- per delayed day. The total amount of Liquidated damages / Penalty to be paid under the provisions of this clause shall not exceed five percent (5%) of the total Contract amount.
16. The bidders are requested to submit their Bank details (RTGS) along with the quotation document.
17. You are informed that there will be no negotiations, so you are requested to submit the final lowest rates for this work.
18. The quotation shall be written on a letterhead of your firm and shall be submitted in a sealed cover superscribing as "Quotation for Vehicle Dept. Office by Renovating Existing General Toilet Unit at S.No.109, Shirdi for Shri Saibaba Sansthan Trust, Shirdi". The reference no. & date of this NIQ shall be mentioned on the envelope. It shall be addressed to **Chief Executive Officer, Shri Saibaba Sansthan Trust, Shirdi, Tal.- Rahata, Dist.- Ahmednagar.**
19. Your quotation should reach at our Shirdi Office on or before 12 /09 /2022

Shri Saibaba Sansthan Trust, Shirdi reserves the right to reject any or all quotations without assigning any reasons therefor.

Thanking you.

Yours Sincerely,



(B.D. Dabhade)

Executive Engineer,

Shri Saibaba Sansthan Trust, Shirdi.

L 9109 J