



SHRI SAIBABA SANSTHAN TRUST, SHIRDI
P.O. Shirdi, Tal.-Rahata, Dist.- Ahmednagar (MS) - 423109.
Tel: (02423) 258899, Fax: 258870.
E-mail: construction@sai.org.in, Website: www.sai.org.in

Notice Inviting Quotations for Construction of Retaining wall in plum concrete masonry at east side of Sainath Chaya Building for Shri Saibaba Sansthan Trust,

Sealed Item rate quotations are invited for the captioned work of Construction of Retaining wall in plum concrete masonry at east side of Sainath Chaya Building for Shri Saibaba Sansthan Trust, You are requested to submit the sealed quotations for the aforesaid work. The detail of work & terms and conditions etc. are mentioned below.

A) Bill of Quantities:

Sr.No	Description	Quantity	Unit
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to adistance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means Removing debris	77.6	Cum
2	Removing lime or lean cement concrete including stacking the spoils as directed with all leads, lifts etc, complete.ing Lean concrete	1.69	Cum
3	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	1.56	Cum
4	Providing random rubble masonry second sort of trap / granite / quartzite / gneiss stones in cement concrete of M10 in superstructure racking out joints when plastering is to be done / striking joints when no pointing or plastering is to be done on the inside watering and scaffolding etc.complete.	27.52	Cum
5	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in plinth as backing in composite masonry including bailing out water manually, striking joints, raking out joints and watering etc Complete.	10.37	Cum
6	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete	2.99	Cum
7	Providing and laying Cast in situ/Ready Mix cement concrete in M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C .coping to plinth or parapet and sill of doors and windows moulded as per detailed drawings or chamfered as approved by the Engineer including steel centering, formwork, cover blocks, laying/pumping, compacting , curing , finishing and roughening them if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / crushed sand VSI Grade finely washed etc	0.3	Cum
Sr.No	Description	Quantity	Unit

8	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc.complete.	42.9	Sqm
9	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	.018	MT
10	Disposal of excavated material up to 3 km.	79.49	Cum

B) Terms & Conditions:

1. The Period for completion of the work shall be sixty working days from the date of work order.
2. The rate shall be inclusive of all material, labour, transport & GST. If any taxes are to be charged extra, it shall be clearly mentioned in the quotation.
3. The bidder should be registered with Employees Provident Fund Organization. The copy of registration should be attached.
4. EMD Rs.2,300/- to be submitted by DD of any Nationalized bank in favor of Chief Executive Officer, Shri Saibaba Sansthan Trust, Shirdi.
5. Security deposit 5% of contract value (2.5% initial) security deposit inclusive of EMD & 2.5% will be deducted from Contractors bill at 5% gross value of the bill.
6. The rates shall be firm and shall not subject to variations.
7. Quantities in BOQ are approximate and may vary according to the requirement. Bill will be paid as per the actual measurement of work executed on site.
8. Defects Liability Period: 01 year from the date of issue of completion certificate by Sansthan.
9. Liquidated Damages: The Liquidated damages to be recovered will be Rs.300/- per delayed day.
10. The working site shall be fenced and protected. The road shall not be used for stacking of materials. For the existing adjoining buildings used by the Shri Saibaba Sansthan Trust / public, proper safety arrangement shall be made. The work activity should not cause any nuisance to other residents and public or cause safety hazard or pollution. The provisions and instructions of any statutory body / agency shall be followed in this regard.
11. Your quotation should reach at our Shirdi Office within 7 days from the receipt of this NIQ.
12. Sealed quotation shall be submitted to the Inward Department of Sansthan at Shirdi.

Shri Saibaba Sansthan Trust Shirdi reserves the right to reject any or all quotations without assigning any reasons therefore.

(D. M. Mugalikar I.A.S.)
Chief Executive Officer,
Shri Saibaba Sansthan Trust, Shirdi.

TO,

Sub:- Notice Inviting Quotations for Construction of Retaining wall in plum concrete**Masonry at east side of Sainath Chaya Building for Shri Saibaba Sansthan Trust,**

Sealed Item rate quotations are invited for the captioned work of Construction of Retaining wall in plum concrete masonry at east side of Sainath Chaya Building for Shri Saibaba Sansthan Trust, Shirdi. You are requested to submit the sealed quotations for the aforesaid work. The details of work & terms and conditions etc. are mentioned below.

A) Bill of Quantities:

Sr.No	Description	Quantity	Unit
1	Excavation for foundation in earth, soil of all types, sand, gravel and soft murum, including removing the excavated material up to adistance of 50 m. beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary back filling, ramming, watering including shoring and strutting etc. complete. (Lift upto 1.5 m.) By Mechanical Means Removing debris	77.60	Cum
2	Removing lime or lean cement concrete including stacking the spoils as directed with all leads, lifts etc, complete.ing Lean concrete	1.69	Cum
3	Providing and laying Cast in situ/Ready Mix cement concrete in M-10 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, Steel centering, formwork, laying/pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / Crushed sand VSI Grade finely washed etc)	1.56	Cum
4	Providing random rubble masonry second sort of trap / granite / quartzite / gneiss stones in cement concrete of M10 in superstructure racking out joints when plastering is to be done / striking joints when no pointing or plastering is to be done on the inside watering and scaffolding etc.complete.	27.52	Cum
5	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in plinth as backing in composite masonry including bailing out water manually, striking joints, raking out joints and watering etc Complete.	10.37	Cum
6	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in	2.99	Cum

	superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete		
7	Providing and laying Cast in situ/Ready Mix cement concrete in M-20 of trap/ granite/ quartzite/ gneiss metal for R.C.C .coping to plinth or parapet and sill of doors and windows moulded as per detailed drawings or chamfered as approved by the Engineer including steel centering, formwork, cover blocks, laying/pumping, compacting, curing , finishing and roughening them if special finish is to be provided and curing complete. (Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/ concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural Sand / crushed sand VSI Grade finely washed etc	0.30	Cu m

Sr.No	Description	Quantity	Unit
8	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 kg per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing for fourteen days scaffolding etc. complete.	42.90	Sq m
9	Providing and fixing in position TMT - FE - 500 bar reinforcement of various diameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. Including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete.	0.02	MT
10	Disposal of excavated material up to 3 km.	79.49	Cum

B) Terms & Conditions:

1. The Period for completion of the work shall be sixty working days from the date of work order.
2. The rate shall be inclusive of all material, labour, transport & GST. If any taxes are to be charged extra, it shall be clearly mentioned in the quotation.
3. The bidder should be registered with Employees Provident Fund Organization. The copy of Registration should be attached.
4. EMD Rs.2,300/- to be submitted by DD of any Nationalized bank in favor of Chief Executive Officer, Shri Saibaba Sansthan Trust, Shirdi.
5. Security deposit 5% of contract value (2.5% initial) security deposit inclusive of EMD & 2.5% will be deducted from Contractors bill at 5% gross value of the bill.
6. The rates shall be firm and shall not subject to variations.
7. Quantities in BOQ are approximate and may vary according to the requirement. Bill will be paid as per the actual measurement of work executed on site.
8. Defects Liability Period: 01 year from the date of issue of completion certificate by Sansthan.
9. Liquidated Damages: The Liquidated damages to be recovered will be Rs.300/- per delayed day.
10. The working site shall be fenced and protected. The road shall not be used for stacking of materials. For the existing adjoining buildings used by the Shri Saibaba Sansthan Trust / public, proper safety arrangement shall be made. The work activity should not cause any nuisance to other residents and public or cause safety hazard or pollution. The provisions and instructions of any statutory body / agency shall be followed in this regard.
11. Your quotation should reach at our Shirdi Office within 7 days from the receipt of this NIQ.
12. Sealed quotation shall be submitted to the Inward Department of Sansthan at Shirdi.

Shri Saibaba Sansthan Trust, Shirdi reserves the right to reject any or all quotations without assigning any reasons therefore.

(D. M. Mugalikar I.A.S.)
Chief Executive Officer,
Shri Saibaba Sansthan Trust, Shirdi.

- 1) Shri Siddheshwar T. Murkute, Shirdi
Rajendra Sonawane, Kopargoan
- 3) Shri Vijay Wamne, Shirdi
Jadhav, Shirdi
- 5) Jay Developer's, Shirdi
Rahata
- 7) Shri Saurabh Tambe, Rahata
Rahata
- 9) Rahul Annasaheb Pagire, Nighoj
Bhavsar, Kopargoan

- 2) Vikrant
- 4) Shri Vishal
- 6) Kaustub Kulkarni,
- 8) Krishikesh Sadaphal,
- 10) Shubham Anil