

To,

Sub – Notice Inviting Quotations for Repairing Cable Trenches at Sai prasadalay, Shirdi.

Sealed quotations are invited for the above work at Shirdi. Subject to the terms and Conditions mentioned below.

Bill of Quantities-

Sr. No.	Description	Quantity	Unit
1	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in plinth as backing in composite masonry including bailing out water manually, striking joints, raking out joints and watering etc. Complete. SSR I.No.27.03	24.33	Cum
2	Providing and laying Cast in situ/Ready Mix cement concreteM-20 of trap/ granite / quartzite/gneiss metal for R.C.C. slabs and landings as per detailed designs and drawings including steel centering, formwork, cover blocks, laying/pumping, compaction finishing the formed surfaces with cement mortar 1:3 of sufficient minimum thickness to give a smooth and even surface or roughening if special finish is to be provided and curing etc. complete,(Excluding reinforcement and structural steel).with fully automatic micro processor based PLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer)etc. complete. With fine aggregate(Crushed sand VSI Grade) SSR I.No.25.70	8.63	Cum
3	Providing sand faced plaster externally in cement mortar using approved screened sand, in all positions including base coat of 15 mm thick in cement mortar 1:4 using waterproofing compound at 1 Kilogram per cement bag curing the same for not less than 2 days and keeping the surface of the base coat rough to receive the sand faced treatment 6 to 8 mm thick in cement mortar 1:4 finishing the surface by taking out grains and curing scaffolding etc. complete SSR I.No.32.11	138	sqm
4	ProvidingandfixinginpositionTMT-FE-500barreinforcementofvariousdiameters for R.C.C. pile caps, footings, foundations, slabs, beams columns, canopies, staircase, newels, chajjas, lintels pardis, copings, fins, arches etc. as per detailed designs, drawings and schedules. including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required complete SSR I.No.26.33	0.90	MT

TERMS AND CONDITIONS-

1. The above rates shall be for completed item inclusive of GST and transport. The rates once quoted shall be firm & no escalation of rates will be entertained.
 2. The Successful bidder has to pay SD Which will be recovered from Bill. Total SD - 5% of Contract amount. SD will be released after 3 months after date of completion of work.
 3. Quantities are approximate and may vary according to requirement. Bill will be paid as per the actual work done.
 4. No advance will be paid against work order. Bill will be paid after completion of all work and upon submission of GST invoice bill.
 5. The time for completion of work shall be 01 Month from the date of issue of the work order
 6. Material shall be strictly as per the above description, specifications mentioned above & prior approval of Engineer In Charge.
 7. In case of any dispute between the parties, the jurisdiction shall vest at Rahata court only
 8. The bidders are requested to submit their Bank details and copy of PAN card, EPF No., and GST Registration No. along with the quotation.
 9. The quotation shall be addressed to The Chief Executive Officer, Shri Saibaba Sansthan Trust, Shirdi, Tal.-Rahata, Dist.-Ahmednagar and written on a letterhead of your firm and shall be submitted on or before 22/11/2025 in a sealed cover super scribing as "Quotation for Repairing Cable Trenches at Sai Prasadalay, Shirdi."
- Thanking you.

(B. D. Dabhade)
Executive Engineer,
Shri Saibaba Sansthan Trust, Shirdi.

Approve by CEO.